No.	Description of work	Per	Rate	Quantity	Cost
			Rs. a. p.		Rs.
4	Burnt stone slabs 5″ to 6″ thick exposed faces dressed two lines and fixed in mortar	S.ft.	0 5 0	104	
5	Burnt brick in lime mortar for superstructure ..	C.ft.	0 4 0	1,650	
6	Providing burnt stone square pillars 10″×10″ and 8 feet high dressed 2 lines with base and capital complete	Each	20 0 0	5	
7	Teakwood doors 5″×6″ door frame work $1\frac{3}{4}$″ thick battened shutters with the other half filled up with $\frac{3}{4}$″ round iron bars completed with fittings including painting	S.ft.	2 0 0	53	
8	Teakwood ventilators 3″×4″ frame work with $\frac{3}{4}$″ iron bars, etc., complete	,,	1 4 0	45	
9	Rolled steel beams and joists of Tata's make, hoisted and fixed	Cwt.	15 0 0	24	
10	Roofing with R.B.C. as per specifications in force 6″ concrete and 2 courses of flat tiles with $\frac{1}{2}$″ plaster..	Sqr.	65 0 0	16.3	
11	Plastering with lime mortar and white-washing ..	,,	3 0 0	24.71	
12	Boxing girders with cement concrete complete	R.ft.	0 6 0	94	
13	Burnt stone slabs 5 to 6 inches thick roughly dressed and fixed in mortar	S.ft.	0 5 0	218	
14	Providing rain water spouts	R.ft.	0 6 0	52	
15	Flooring with cement concrete of $1\frac{1}{2}$″ thick (1 : 2 : 4) on 3″chunam concrete bed with $\frac{3}{8}$″ thick red cement plastering cut to the required pattern	Sqr.	20 0 0	9.26	
16	Deep cement pointing to masonry	,,	3 0 0	1.94	
17	Making necessary alterations	L. S.	..	..	
18	Electric connection	,,	..	..	

P. RAJAGOPALAN,
Executive Engineer.

CHITALDRUG DIVISION.

Notification dated 20th February 1940.

1. Sealed tenders will be received at the Office of the Executive Engineer, Chitaldrug Division, up to 3 P.M. on 9th March 1940, for constructing Linemen's quarters at Anagod and Vijapur on Davangere-Chitaldrug transmission line.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Chitaldrug Division, should be addressed to the Executive Engineer, Chitaldrug Division, in a sealed cover and superscribed as "Tender for constructing Linemen's quarters at Anagod and Vijapur on Davangere-Chitaldrug transmission line." The name of the tenderer should also be superscribed on the top of the cover.

3. Each tender must be accompanied by a duplicate Treasury challan only after having paid the deposit of Rs. 200 for each work in cash to the credit of "17 (a) P. W. Deposit" or Government Promissory Notes or Mysore Government Bonds, duly endorsed at face value or market value, whichever is less, as earnest money and the balance up to 10 per cent will be reserved in the bills of the successful tenderer. The earnest money of the successful tenderer will be retained as security deposit for the due fulfilment of the contract. Such a deposit in cash will not carry any interest.

4. The tenders will be opened in the presence of such tenderers who wish to be present on 9th March 1940 at 3-30 P.M. The final acceptance of the tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any.

5. The name of the successful tenderer will be posted on the Notice Board in the Executive Engineer's Office in due course. Within eight days of the acceptance of the tender, the successful tenderer will be required to execute an agreement in the departmental Schedule Contract Form, for the due fulfilment of the contract, and for the execution of all items of work in accordance with the Bombay Specifications (1931).

6. Failure to comply with the condition 5 above or to agree to carry out the work in accordance with the specifications and agreements in force, will entail forfeiture of the earnest money.

7. The earnest money of rejected tenders will be returned on submission of the receipt originally granted, along with an application to the Executive Engineer.

8. Copies of contract documents, schedules and drawings may be seen at any time at the Executive Engineer's Office, Chitaldrug, on all working days between 11 A.M. and 5 P.M. and may be obtained from that officer on payment of Re. 0-4-0.

9. Specific rates should be given for each item in the schedule accompanying the tender and the rates should be in rupees, annas and pies and expressed in words and figures. Tenders offering a percentage reduction on the estimate amount will be rejected.

10. Any rates or lumpsum amounts for the items not called for, if tendered by the tenderer, will not be taken notice of. The rates for such items may be entered in a separate schedule with date and reasons for the same.

11. No alterations which are made by the tenderers in the tender form in the nomenclature of the items of work will be recognised and if corrections are made, the tenders are liable to rejection.

12. There should be no alterations or erasures in the tenders in the rates of items and any corrections made in the rates should be attested to, and the number of corrections, if any, in each page noted at the foot of the same by the tenderer.

13. No reference should be made to the Public Works Department schedule of rates.

14. In the event of the tender being submitted by a firm, it must be signed separately and severally by each member thereof or in the event of absence of any partner, it must be signed on his behalf by a person holding power-of-attorney authorising him to do so.

15. When once the rates tendered have been accepted, they will not be revised under any circumstances. In regard to items of work not tendered, the rates for the same will be calculated by the Executive Engineer on the basis of current rates for materials and labour with a contractor's profit of 5 per cent as may be approved by the Superintending Engineer. This shall be final and legally binding on the tenderer.

16. The quantities given in the schedule are only approximate and the drawings shown to the contractor are only tentative and are liable to alterations, omissions, deductions or additions, at the discretion of the Executive Engineer or his representative. The tendered rates will hold good for any quantity, whether higher or lower than those given in the enclosed schedule.

17. The works should be completed and handed over in a tidy condition to the Public Works Department by the end of December 1940, failing which the Executive Engineer may, at his discretion, levy a penalty of Rs. 25 per day which will ordinarily be calculated at 12 per cent per annum on the total outlay as liquidated damages for non-fulfilment of contract, and will be recovered from the contractor's outstandings for the period exceeded by him beyond the time fixed and until the work is completed and handed over.

18. In all matters of disputes of any kind not specially provided for in the agreement or of rates, penalties, measurements, quality of work, etc., the decision of the Chief or the Superintending Engineer shall be final and legally binding.

19. No claim for damages for delays caused by officers of the department in the execution of the work will be considered, whatever may be the reasons for such delays. Contractors should bear this in mind when tendering for the work. Extension of time due to delays caused by the departmental officers will, however, be considered on the merits of each case.

20. The contract should not be sublet.

21. All materials, tools and plant and machinery that will be supplied by the Executive Engineer in the interest of the work shall be accepted by the tenderer at the rates fixed by the Executive Engineer. The tenderer will pay the hire on tools and plant and machinery as per rules from the date of taking over of such machinery, tools and plant from the Stores to the date of return thereto, the dates considered being the dates of acknowledgments of the vouchers in each transaction.

22. The contractor should arrange for the payment of royalty and tolls.

Note.—(*a*) The contractor should at his own cost—

(1) Provide rods, stakes, ropes and labour required in setting out the works.
(2) Provide all necessary scaffolding, centering, labour and appliances for hoisting.
(3) Provide mortar mills and sheds, to keep materials under cover and also for workmen.
(4) Arrange for protecting work during inclement weather.
(5) Supply requisite temporary lights, water cisterns, water pumps and hoses, sieves, parahs, shoring, strutting and other requisite protective appliances during the progress of the work.
(6) Supply all water required for work and workmen and shall provide temporary latrines and drains.
(7) Clean away all dirt, rubbish, superfluous materials and debris as they accumulate.
(8) Provide arrangements for pumping and baling of water from excavations and foundations wherever and whenever necessary with his own pumping apparatus including necessary leading drains, slump pits, etc.
(9) Afford facilities to any other parties employed upon the work by the P. W. D., so that their work may proceed during the progress of the contract, and give such persons the use of ordinary scaffolding and ladders.
(10) The contractor is responsible for all accidents to workmen, etc., on the work and he must take precaution against all risk of accidents and if necessary provide for the same by insurance at the proper time.

Note.—(*b*) It is the business of the contractor to make his own arrangements for quarries and supplies of materials.

23. Chamundi Brand cement alone to be used.

24. All lumpsum items will be measured and paid for at the minimum schedule rates.

Abstract estimate of the probable cost of constructing one and half block of line-men's quarters to accommodate six coolies at Anagodu on the Davangere-Chitaldrug transmission lines.

Serial No.	Items of work	Per	Rate	Quantity	Tender rate in	
					Figures	Words
	I. *At Anagodu.* (*The details of quantities are for one block.*)		Rs. a. p.		Rs.	Rs.
1	Earthwork excavation and filling in basement	C.yd.	0 3 0	29		
2	Concrete stone jelly in lime mortar 1 : 2	C.ft.	0 3 0	309		
3	Stone in clay foundation and basement including bond stones	„	0 3 0	741		
4	Burnt brick in clay superstructure	„	0 4 0	1,533		
4*a*	Burnt brick in lime mortar superstructure	„	0 4 0	510		
5	Stone slabs 4″ thick roughly dressed and fixed in mortar	S.ft.	0 8 0	21		
6	Chunnam plastering (2 coats)	Sqr.	3 0 0	43·14		
7	Cement pointing with thread lining	„	4 0 0	2·07		
8	White and colour washing 2 coats (as per plastering and pointing)	„	0 4 0	44·64		
9	Roofing with first class Mangalore tiles on T. W. reepers 2″×1″ including wood oiling	„	24 0 0	15·00		
10	Ridge tiles set in mortar and cement pointed complete	R.ft.	0 8 0	78		
11	Ventilating tiles, big size, fixed, etc., complete	„	2 0 0	16		
12	T. W. work wrought and put up including 2 coats of wood-oiling	C.ft.	5 0 0	65·13		
13	T. W. doors battened 1″ thick shutters with all fixtures complete (frames 3″×4″ or flat iron clamps 1″ long and 2″ wide)	S.ft.	1 2 0	156		
14	T. W. battened windows 1″ thick shutters and $\frac{5}{8}$″ iron bars with all fixtures, complete	„	1 8 0	75		
15	T. W. shelves with shutters and shelf planks, etc., complete	„	1 2 0	60		
16	Chocolate painting, 2 coats	Sqr.	4 0 0	7·52		
17	Constructing sinks in bath rooms, complete.	Each	5 0 0	4		
18	Providing stone mortar and pestle, complete.	„	5 0 0	4		
19	Flooring with 3″ lime concrete (1 : 3) and 1$\frac{1}{2}$″ cement concrete (1 : 2 : 4) on top with $\frac{1}{2}$″ cement plastering (1 : 3) on top complete (with red ochre colour)	Sqr.	20 0 0	5·5		
20	Do (without red ochre colour)	„	18 0 0	2·5		
21	Levelling ground, etc.	As per actual work				
22	Providing and fixing T. W. planks with T. W. pegs, etc., complete	S.ft.	0 8 0	100		
23	Constructing 'V' shaped drain 4″ lime concrete as per specification	R.ft.	0 8 0	70		
24	Chunam patty brick in lime mortar 3″×6″ plastered, etc., complete	„	0 4 0	125		
25	Excavating soakage pits 5′×5′×6′ and filled with brickbats of 1$\frac{1}{2}$″ to 2″ size well burnt and covered with 1″ thick red earth connecting the drain to it with a galvanised pipe 3″ to 4″ diar. and an iron grating at the entrance, etc., complete	As per actual work				

Abstract estimate of the probable cost of constructing one and half block of line-men's quarters to accommodate six coolies at Vijapura on the Davangere-Chitaldrug transmission lines.

	II. *At Vijapura.* (*The details of quantities are for one block.*)		Rs. a. p.		Rs.	Rs.
1	Earthwork excavation and filling in basement	C.yd.	0 3 0	23		
2	Concrete stone jelly in lime mortar 1 : 2	C.ft.	0 3 0	309		
3	Stone in clay foundation and basement including bond stones	„	0 3 0	741		

Sl. No.	Items of work	Per	Rate	Quantity	Tender rate in	
					Figures	Words
			Rs. a. p.		Rs.	Rs.
4	Burnt brick in clay superstructure ..	C. ft.	0 3 0	1,533		
4a	Burnt brick in mortar superstructure ..	,,	0 4 0	510		
5	Stone slabs 4″ thick roughly dressed and fixed in mortar	S.ft.	0 8 0	21		
6	Chunam plastering (2 coats)	Sqr.	3 0 0	43.14		
7	Cement pointing with thread lining ..	,,	4 0 0	2.07		
8	White and colour washing 2 coats (as per plastering and pointing)	,,	0 4 0	44.64		
9	Roofing with first class Mangalore tiles on T. W. reepers 2″×1″ including wood oiling	,,	24 0 0	15.00		
10	Ridge tiles set in mortar and cement pointed complete	R.ft.	0 8 0	78		
11	Ventilating tiles big size, fixed, etc., complete	,,	2 0 0	16		
12	T. W. work wrought and put up including 2 coats of wood-oiling	C.ft.	5 0 0	65.13		
13	T. W. doors battened 1″ thick shutters with all fixtures complete (frames 3″×4″ or flat iron clamps 1″ long and 2″ wide ..	S.ft.	1 2 0	156		
14	T. W. battened windows 1″ thick shutters and $\frac{5}{8}$″ iron bars with all fixtures complete ..	,,	1 8 0	75		
15	T. W. shelves with shutters and shelf planks, etc., complete	,,	1 2 0	60		
16	Chocolate painting, 2 coats	Sqr.	4 0 0	7.52		
17	Constructing sink in bath rooms complete	Each	5 0 0	4		
18	Providing stone mortar and pestle complete	,,	5 0 0	4		
19	Flooring with 3″ lime concrete (1 : 3) and $1\frac{1}{2}$″ cement concrete (1 : 2 : 4) on top with $\frac{1}{2}$″ cement plastering (1 : 3) on top complete (with red ochre colour)	Sqr.	20 0 0	5.5		
20	Do (without red ochre colour)	,,	18 0 0	2.5		
21	Levelling ground, etc.	As per actual work.				
22	Providing and fixing T. W. planks with T. W. pegs, complete	S.ft.	0 8 0	100		
23	Constructing 'V' shaped drain 4″ in lime concrete as per specification	R.ft.	0 8 0	70		
24	Chunnam patty brick in lime mortar 3″×6″ plastering, etc., complete	,,	0 4 0	125		
25	Excavating soakage pits 5′×5′×6′ and filled with brickbats of $1\frac{1}{2}$″ to 2″ size well burnt and covered with 1″ thick red earth connecting the drain to it with a galvanised pipe 3″ to 4″ dia. and an iron grating at the entrance, etc., complete..	As per actual work.				

B. TIRUMALACHAR,
Executive Engineer.

MISCELLANEOUS DEPARTMENTS.

SRI NARASIMHARAJA HOSTEL, BANGALORE.

Notification No. 552, *dated* 20*th February* 1940.

Attention of the public is invited to the tender Notices published in pages 334 to 337, Part VI of the *Mysore Gazette*, dated the 15th February 1940, calling for the supply of provisions, curds and milk vegetables and stationery to the Sri Narasimharaja Hostel, Bangalore, for the year 1940-41.

M. S. RAJAGOPAL RAU,
President.